

Appendix 2

Navigational Risk HAZID Workshop

DET NORSKE VERITAS

Navigational and Safety Risk Assessment

Washington State Ferries



Abbreviations

AIS Automated Information System

BC British Columbia

DNV Det Norske Veritas

HAZID Hazard Identification (workshop)

HC Hydrocarbon

LNG Liquefied Natural Gas

PSE Puget Sound Energy

SMS Safety Management System

USCG United States Coast Guard

VTS Vessel Traffic Services

WSDOT Washington State Department of Transportation

WSF Washington State Ferries

DET NORSKE VERITAS

Navigational and Safety Risk Assessment

Washington State Ferries

MANAGING RISK



Τα	Page	
1	INTRODUCTION	4
2	HAZID WORKSHOP	4
	2.1 Scope	4
	2.1.1 Geographic	4
	2.1.2 Incident Type	11
	2.2 Participants	12
	2.3 Guidance on Hazard Identification	13
3	HAZID FINDINGS	14
	3.1 General Findings	14
	3.2 Anacortes/San Juan Islands/Sidney	16
	3.3 Seattle/Bremerton	18
	3.4 Mukilteo/Clinton	19
	3.5 Fauntleroy/Vashon/Southworth	20
	3.6 Edmonds/Kingston	
	3.7 Eagle Harbor Approach Including Environmental Issues	
4	HAZID CONCLUSION	23

Navigational and Safety Risk Assessment

Washington State Ferries



1 INTRODUCTION

DNV conducted a navigational risk assessment to obtain stakeholder input for the safety and security assessment. As part of the navigational risk assessment, a navigation HAZID workshop was held in Seattle, February 13, 2013 with local maritime experts to identify local hazards related to the ferry routes and to assess how the hazards could influence risk.

A navigation HAZID workshop utilizes a systematic approach to identify hazards and assessment of associated risks in order to provide information to aid decision making concerning the need for risk reduction measures.

Results of the navigation HAZID helped establish relevant probability values for accidental incidents along the sailing route and at the terminal. Existing safeguards and barriers were identified as well as needs for risk reducing measures.

2 HAZID WORKSHOP

A Hazard Identification Study (HAZID) is the process of identifying hazards in order to plan for, avoid, or mitigate their impacts. Hazard identification is an important step in risk assessment and risk management.

Therefore the navigation HAZID workshop was a key step and provided risk assessors important local knowledge about the sailing route, highlighting particular navigational challenges along the sailing route and approaches to the terminals.

2.1 Scope

09 October 2013

The scope was defined in terms of both geographic extent and incident type.

2.1.1 Geographic Extent

All the evaluated ferry routes are shown in Figure 2-1 to Figure 2-3. The geographic boundary for the HAZID workshop was the following ferry routes:

- Anacortes, Washington San Juan Islands, Washington Sidney, British Columbia, Figure 2-4 to Figure 2-6
- Seattle, Washington Bremerton, Washington, Figure 2-7
- Mukilteo, Washington Clinton, Figure 2-8
- Vashon, Washington Fauntleroy, Washington, Figure 2-9
- Edmonds, Washington Kingston, Washington, Figure 2-10
- Eagle Harbor approach, not shown in a dedicated figure

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01
Appendix 2 Navigational Risk HAZID Workshop





Figure 2-1 Route Segments Schematic

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01






Figure 2-2 Route Segments Southern Portion

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01






Figure 2-3 Route Segments Northern Portion






Figure 2-4 Anacortes/Lopez Route




Figure 2-5 San Juan Islands Ferry Routes

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01 $\,$






Figure 2-6 Friday Harbor/Sidney Ferry Route




Figure 2-7 Seattle/Bremerton Ferry Route

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01






Figure 2-8 Mukilteo- Clinton Ferry Route




Figure 2-9 Fauntleroy/Vashon/Southworth Ferry Route

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01 $\,$






Figure 2-10 Edmonds/Kingston Ferry Route

2.1.2 Incident Type

The following incident types were considered in the workshop:

- Collision with other vessel(s)
- Allision with a terminal or another object
- Powered grounding. This is a grounding that may occur when a ship has the ability to navigate safely yet goes aground, due to for example, human error.
- Drifting grounding. This is a grounding that may occur when a ship is unable to navigate safely, usually due to mechanical failure, and is forced onto the shoreline by the action of wind or waves.

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01

Appendix 2 Navigational Risk HAZID Workshop

2.2 Participants

A HAZID participant group was assembled of 24 local experts who were knowledgeable about the study area. Members of the team had experience in piloting, escorting, and conning vessels within WSF's ferry network and working on marine projects in the Seattle and coastal areas. The participants' experience covered a wide range of maritime background and detailed knowledge about the area. The participant group was appropriate to assess the hazards involved in navigation in the area.

Table 2-1 List of Navigational HAZID Participants

Name	Company	Position	E-mail
Peter Hoffmann	DNV	Facilitator	Peter.Nyegaard.Hoffmann@dnv.com
Per Sollie	DNV	Scribe / Project Manager	Per.Sollie@dnv.com
Christopher Lanza	DNV	Security Analyst	Christopher.Lanza@dnv.com
Mark Ashley	USCG	VTS Director	Mark.E.Ashley@uscg.mil
Greg Peterson	BC Ferries	Director, Fleet Performance	Greg.Peterson@bcferries.com
Brad Judson	BC Ferries	Manager, SMS	Brad.Judsen@bcferries.com
Cotty Fay	WSF	Chief Naval Architect	faye@wsdot.wa.gov
Parrek Kimmerly	WSF	Vessel Master	kimmerd@wsdot.wa.gov
John Veentjer	MXPS	Director	jeveentjer@marexps.com
Torn Larsen	FAC	Member, Ferry Advisory Committee	t.larsen@neotri.com
Chip Boothe	DOE	Spill Prevention Response Manager	cboo461@ecy.wa.gov
Jonathan Ward	PSP	President	president@pspilots.org
Gretchen Bailey	USCG	CID	Gretchen.M.Bailey@uscg.mil
John Dwyer	USCG	OCMI	John.D.Dwyer@uscg.mil
Lindsay Cook	USCG	Inspector	Lindsay.N.Cook@uscg.mil
Vern Day	WSF	Sr. Port Engineer	day@wsdot.wa.gov
Steven Hopkins	WSF	Staff Master	Hopkin@wsdot.wa.gov
Rand Lymangrover	Tote	Terminal Manger	rlymangrover@totemocean.com
John Dwyer	USCG	OCMI	John.D.Dwyer@uscg.mil
Noel Brady	WSDOT	Communications	Bradyn@wsdot.wa.gov
Carol Lee Roalkvam	WSDOT	WSDOT Policy Branch Manager	Roalkvc@wsdot.wa.gov
Kelly Mitchell	WSF	Sr. Port Captain	Mitchek@wsdot.wa.gov
Sheila Helgath	WSF	Environmental Program Manager	HelgatS@wsdot.wa.gov
Darnell Baldinelli	WSF	Safety Systems Engineer	BaldinD@wsdot.wa.gov

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01

Appendix 2 Navigational Risk HAZID Workshop

Navigational and Safety Risk Assessment

Washington State Ferries



2.3 Guidance on Hazard Identification

The following categories were used to aid in the identification of hazards:

- Human error
- Steering failure
- Propulsion failure
- Communication / navigation failure
- Mechanical/electrical failure
- Environmental conditions
- Shipboard emergency
- External influence

Four types of important contextual considerations were applied during the workshop:

External / Physical Conditions

Wind direction and strength
Wave direction and intensity
Current direction and intensity/ effect of tide
Route geometry (depth, width, turns)
Route marking (lights, marks, buoys,
day/night/winter/summer navigation)
Fog/snow/reduced visibility
Accident prone areas (bends and turns)
Power cables (subsea/air)

Existing Mitigations

International rules and regulations
Port and traffic rules
Traffic monitoring
Pilotage rules

Characteristics of LNG-fueled Passenger Ferry Vessels

Limitations on draughts, summer/winter
Air draughts (ballast)
Length, turning characteristics, maneuverability
(machinery, rudder)
Emergency anchor
Stopping distance
Visibility from bridge
Main/aux engine, steering machinery

Potential Hazards

Number and types of vessels in the fairways
Fixed objects
Hazardous cargo
Maneuvering areas (meeting/crossing)
Human factors (competence, charts, fatigue, language, quality/availability of pilots)
Grounding

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01

Appendix 2 Navigational Risk HAZID Workshop

3 HAZID FINDINGS

To assist organization of the HAZID discussion, the ferry routes were predefined into sailing route segments:

- Anacortes San Juan Islands and to British Columbia
- Seattle / Bremerton
- Mukilteo / Clinton
- Vashon / Fauntleroy
- Edmonds / Kingston
- Eagle Harbor approach

Sailing route traffic and type information was provided for each segment. Each segment was discussed; potential hazards identified noting any segment specific causes. Based on the causes, each segment was assigned a rating, in terms of the likelihood of a hazard leading to a grounding or collision incident using the following system:

Much higher than average -	H-3
Higher than average -	H-2
Average -	A-1
Lower than average -	L-2
Much lower than average -	L-3

Section 3.1 describes the general findings from the HAZID. Sections 3.2 to 3.7 present the HAZID worksheets.

3.1 General Findings

The following issues were raised as part of general discussions across the various segments:

- The risk for an allision/collision in Elliot bay (i.e. Seattle Bremerton route) would be of the highest of all the WSF routes, due to the high traffic density.
- No immediate Hot Wash will be initiated if an incident occurs, however lessons learned after incidents are entered into a WSF database and used to develop training of personnel.
- For situations such as black ship, loss of propulsion etc., tow gear is available on the Ferries in order to get help from tugs or other vessels.
- Emergency anchors will probably not work in most areas due to water depth; however if used they will not be possible to hoisted from the Ferry. This Anchor use would be the last resort in case of a drifting incident.
- All bridges on the ferries are identical similar system wide in configuration and layout for standardization purposes. Thus reducing the time for bridge crew to be aquatinted with

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01

Appendix 2 Navigational Risk HAZID Workshop

DET NORSKE VERITAS

Navigational and Safety Risk Assessment

Washington State Ferries

MANAGING RISK

equipment if new ferries are entered in a given route. All crews receive route and vessel familiarization training before being assigned to a specific vessel.

- Vessel Captains and Mates generally have years of experience with the vessels and routes to
 which they are assigned. This experience and local knowledge reduces the potential for human
 error.
- Sea trials are performed after each overhaul and major maintenance in order to check the maneuverability and functionality of the vessel.
- The WSF ferries have a standing order to avoid a potential collision situation by sailing aft of any ship which they cannot pass more than 1 nautical mile ahead of ,even if the ferries have the right of way.
- Generally, the primary collision risk is related to crossing the main shipping lanes in the area. These are covered by VTS and the majority (if not all) the commercial traffic using the traffic lanes have a pilot on-board.
- Fishing boats including fishing equipment from local fishermen are seen as an issue concerning navigation of ferries during the fishing season. This is seen as a navigation issue rather than a potential direct cause of an LNG release.
- An allision incident is claimed to occur about every 18 months in the total fleet of ferries, mainly due to the high number of terminal approaches performed by all ferries
- No objects, overhangs, bridges or similar were identified in normal operation which could potentially hit the LNG tank if the ferries got too close
- For the Eagle Harbor site, a short environmental review was discussed regarding emission of gas (venting) and incidental discharges of dry chemicals. WSF will need to investigate the potential regulations and impacts from emissions related to any maintenance activities that could release natural gas.

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01

Appendix 2 Navigational Risk HAZID Workshop



4 HAZID WORKSHEETS

The HAZID Worksheets below document the results and reflect the information gathered in the workshop. Information in [brackets] was added to or removed from the worksheets by comment after the workshop.

4.1 Anacortes/San Juan Islands/Sidney

#	Hazard/Description	Cause	Mitigation	R#	Comments
		Ana	cortes to Lopez		
1	Collision with other vessel	Traffic to/from Anacortes terminal	Strict departure rules, VTS special areas, additional traffic measures in place, one way traffic only, procedures tugs and tows, ferries must pass astern deep draft vessels, tank vessels are escorted with tugs, speed limits on tankers 11 knots. AIS.	H-2	Commercial fishing vessels to and from Alaska, Petroleum tankers, tug and tows, dry bulk. Mostly recreational traffic out in the islands.
2	Grounding	Harsh weather	Short loading, less vehicles in the bow, bringing the bow up to avoid green water	H-2	Obstruction Pass is a "storm route" during heavy weather.
3	Allision	Currents right outside the dock line at Anacortes	Damage to Vessel or Dock	H-2	12,000 – 13,000 ferry arrivals per year,
4	Collision	Main tanker route passes, minimum 1 tanker a day through Rosario Strait		H-2	
		Frida	y Harbor - Orcas		
5					Friday Harbor is sheltered, low current, major marina, float planes can be an issue, a lot of condos in Friday Harbor (could be a LNG consequence). In Orcas there is a diesel holding tank.

DET NORSKE VERITAS

Navigational and Safety Risk Assessment

Washington State Ferries

MANAGING RISK



#	Hazard/Description	Cause	Mitigation	R#	Comments	
	Anacortes - Orcas Friday Harbor - Sydney					
7	Collision with other vessel			H-2	Traffic around Shaw Island, yachts, whale watchers	
8	Allision			H-2	Lopez has a strong current making landings a bit difficult	
9	Power grounding			H-2	Shaw Island has grounding potential	
10	Power grounding			H-2	Wasp Pass has grounding potential, captains may divert through San Juan channel to enter Orcas port.	
		Sidney	v – Friday Harbor			
11	Collision with other vessel		VTS has a handoff line with Canada at Haro Strait	H-2	Traffic will be expanded in BC in the near future	
12	Collision with other vessel		Two pilots required for Canadian Tankers, tug escort for a loaded tanker as well	H-2	West of Haro strait the ground is basically sand banks.	
13	Power grounding			H-2	Simple straight forward navigation to Sidney. Protected waters after passing the straight	
14	Collision with other vessel			H-2	A lot of recreation traffic in the Sidney vicinity. BC ferries will be operating at a distance from WSF.	

H-3 Much higher than average -Higher than average -H-2 Average -A-1 L-2 L-3 Lower than average -Much lower than average -

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01
Appendix 2 Navigational Risk HAZID Workshop
09 October 2013

Navigational and Safety Risk Assessment

Washington State Ferries

MANAGING RISK



4.2 Seattle/Bremerton

#	Hazard/Description	Cause	Mitigation	R#	Comments
1	Collision in Elliot Bay	Human error (communications)	AIS, Traffic control, VTS measures, Communications, Traffic separation schemes, 1 nm clearance required	H-2	Seattle is a major terminal, fast ferries, tankers, bulkers, yachts, large marina, [oil and gravel barges,] and cruise ships
2	Grounding in the Rich passage	Steering failure, fog	Well marked route, redundant steering gear, front and aft propellers, radar, bow propellers engaged during fog conditions, at limited visibility will post more people on the bridge	H-2	Sounding of fog signal when visibility is less than a mile. Tug response will come out of Seattle, Elliot Bay.
3	Collision with pleasure craft	Human error (communications)	[Lookout, ferry whistle, and loudspeaker]	H-2	Float planes in Elliot Bay could also be an issue.
4	East/West bound Ferry North/South bound deep draft	Human error (communications)	Pilots, increased VTS service, radio communication	H-2	All commercial vessels are required to have a pilot. Coleman dock is assumed to be the highest risk.
5	Collision with Tribal Vessels	Human error (communications)	Protocol on tribal fishing vessels [generally smaller vessels, and are less of a threat], reflective signage on trawling gear	H-2	
6	Collision with Military vessel at Rich Pass	Communications	[VTS notification in advance by military]		[Naval vessels sometimes escorted]

Much higher than average -H-3 H-2 Higher than average -Average -A-1 Lower than average -L-2 Much lower than average -L-3

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01 $\,$

Washington State Ferries

MANAGING RISK



4.3 Mukilteo/Clinton

#	Hazard/Description	Cause	Mitigation	R#	Comments
1	Collision with other vessels	[Human error]	[Training, detailed SMS policies and procedures]	L-2	Naval traffic, tugs and tows are the main traffic. 2 vessels per day.
2	Allision	[Human error]	[Training, detailed SMS policies and procedures]	L-2	Floating dolphin on Mukilteo side. Mukilteo dock will be moved in the next 5 years. Will be more sheltered, but still be a single slip dock. The current issue could be mitigated.
3	Drift grounding	[Loss of propulsion]	[Most routes have one or more ferries operating nearby that can render assistance.]	L-2	Spring runoff can create a lot of current
4	Grounding	[Human error]	[Training, detailed SMS policies and procedures]	L-2	No hard ground, friendly edges. High frequency, 12 min crossing, 15 min loading, three hours downtime at night.
5	Collision with recreational traffic	Ferry traffic, traffic in out of sand heads, congested	VTS monitoring considered adequate	L-2	

Much higher than average -H-3 Higher than average -H-2 Average -Lower than average -A-1 L-2 Much lower than average -L-3

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01
Appendix 2 Navigational Risk HAZID Workshop
09 October 2013

Washington State Ferries

MANAGING RISK



4.4 Fauntleroy/Vashon/Southworth

#	Hazard/description	Cause	Mitigation	R#	Comments
1	Collision/Allision with berth	Human error, lack of knowledge of the vessel or route	SMS procedures, Annual training, Concrete and Steel terminals to withstand shear loads (designed up to 5kts)	A-1	
2	Allision with the docks	Human error, lack of knowledge of the vessel or route	Where incidents have occurred these have been introduced in the annual training.	A-1	Risk reduction measure: Personnel to attain more familiarity with the vessel and local procedures.
3	Collision with Ferry between Southworth and Vashon with northbound traffic from Tacoma and mainly Olympia	Visibility, Complexity of the schedule, Human error	VTS, AIS, SMS procedures, Pilots	Н-2	Deep drafts will be heading to Tacoma. Visibility is usually good. Southbound vessels will be at a lower speed, all Tacoma bound vessels will have pilots onboard. All southbound vessels will be already slowing down. North bound vessels will be at 12 - 15 knots.
4	Grounding	Human error, lack of knowledge of the vessel or route	[Training, detailed SMS policies and procedures]	H-2	No immediate Hot Wash after incident. Lessons learned are entered into a WSF database and used to develop training.

H-3 H-2 Much higher than average -Higher than average -Average -A-1 Lower than average -L-2 Much lower than average -L-3

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01 $\,$

Navigational and Safety Risk Assessment

Washington State Ferries

MANAGING RISK



4.5 Edmonds/Kingston

#	Hazard/Description	Cause	Mitigation	R#	Comments
1	Collision with Vessels to/from Tacoma, Olympia or Seattle	Human error or Mechanical error	Traffic separation scheme, emission , VTS (add this into all collisions and groundings)	A-1	Normal speed for vessels would be 20 knots or below (container ships). 14 crossings a day (northbound/southbound).
2					Multiple berths on Kingston side. Edmonds has concrete dolphins. Soft bottom on both sides.
3	Collision with Fishing Vessels in the Fall	Human error	Visual	A-1	Cloudier and more wind than other ports (some swell and wind). Wind is usually not an issue for shutting down the route.
4					On Kingston side there is a large marina. There is a railroad crossing close to the pier (potential LNG consequence)

H-3 Much higher than average -Higher than average -H-2 Average -A-1 Lower than average -L-2 Much lower than average -L-3

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01 $\,$

Washington State Ferries

MANAGING RISK



4.6 Eagle Harbor Approach Including Environmental Issues

#	Hazard/description	Cause	Mitigation	R#	Comments
1	Grounding	Human error, Fog, Mechanical error	Redundant steering gear, redundant propulsion, controlled entry	A-1	No commercial traffic, strictly recreational and WSF traffic. Ground is mainly rock and sand. Channel is deep, approx. 30 ft. E and F slips can be difficult to maneuver into.
2	Collision	Human error, recreational vessel fails to give way	Audible signal from ferry	A-1	
3	Collision with log tow	Human error	Audible signal from ferry	A-1	
4	LNG spillage	Leakage Collision			This topic is discussed in the Terminal and Safety assessment.
5	Emission of gas	Venting of natural gas			WSF to investigate whom and which authorities to contact regarding LNG/HC emissions. PSE might have some insight. Are there any regulations of HC emissions in the state/federal regime? Regulatory implications could be an issue.
6	Incidental discharges of dry chemicals	Firefighting drills	[Would be covered under the Vessel General Permit.]		

Much higher than average -H-3 Higher than average -H-2 Average -A-1 Lower than average -L-2 Much lower than average -

Reference to part of this report which may lead to misinterpretation is not permissible. DNV ref.: PP061307- 2, Rev 01 $\,$

5 HAZID CONCLUSIONS

The seven segments were rated overall as follows:

•	San Juan Islands and to BC	Above average risk due to high level of traffic out of Anacortes and in the Haro Strait as well as the grounding risk around the San Juan Islands
•	Seattle – Bremerton	Above average risk due to the high density of traffic within the Seattle Harbor area and crossing the main shipping lanes as well as additional grounding risk in Rich Pass
•	Mukilteo – Clinton short route	Lower than average risk due to reduced traffic in this area and
•	Vashon – Fauntleroy	Average risk - benign navigational challenges overall
•	Edmonds – Kingston	Average risk - benign navigational challenges overall
•	Eagle Harbor approach	Average risk - benign navigational challenges overall

The key observations from the HAZID were as follows

- In the event of a black ship, loss of control or allision, no objects such as cliffs, rock formations, overhung objects such as container cranes, dock cranes or similar were identified during the course of the workshop that could act as a threat of impact on the two top mounted LNG tanks
- The main collision risks are related to crossing of the main shipping lanes. These are covered by VTS in all areas and the WSF ferries have a standing order to pass behind crossing traffic if safe passage more than 1 nautical mile ahead is not possible. In addition, most of the traffic in the shipping lanes will have pilots onboard.
- Allision with the berth at either end of the crossings seems to be the most frequent incident, however it poses minimal damage potential to an LNG tank.
- No objects, overhangs, bridges or similar were identified in normal operation which could potentially hit the tank if the ferries got too close.
- Transit in Rich Pass and San Juan Island areas was identified as having the greatest grounding risk.
- Master and Mates primarily sail on one given route on all rotations, and a special crew with knowledge of all routes is at hand if replacements are needed. This reduces the risk of errors due to lack of local knowledge.

Reference to part of this report which may lead to misinterpretation is not permissible.

DNV ref.: PP061307- 2, Rev 01

Appendix 2 Navigational Risk HAZID Workshop

Det Norske Veritas:

DNV is a global provider of knowledge for managing risk. Today, safe and responsible business conduct is both a license to operate and a competitive advantage. Our core competence is to identify, assess, and advise on risk management, and so turn risks into rewards for our customers. From our leading position in certification, classification, verification, and training, we develop and apply standards and best practices. This helps our customers to safely and responsibly improve their business performance.

Our technology expertise, industry knowledge, and risk management approach, has been used to successfully manage numerous high-profile projects around the world.

DNV is an independent organisation with dedicated risk professionals in more than 100 countries. Our purpose is to safeguard life, property and the environment. DNV serves a range of industries, with a special focus on the maritime and energy sectors. Since 1864, DNV has balanced the needs of business and society based on our independence and integrity. Today, we have a global presence with a network of 300 offices in 100 countries, with headquarters in Oslo, Norway.

Global impact for a safe and sustainable future: